

GOVERNMENT OF ODISHA

Tender Inviting Authority: Panchayat Samiti ,Bhubaneswar

Name of Work: " Completion of Baranga College in Dadha Gram Panchayat,Dadha G.P.."

Bid identification No: - Panchayat Samiti , Bhubaneswar /03

Bidder Name:

Sl. No.	Description of work	No.or	Unit	Estimated Rate(in Rs.)		Amount	
		Qty.		Figure	Words	Rs.	P
1	2	3	4	5	6	7	
<u>A- CIVIL WORK</u>							
1	Providing and laying plain cement concrete of proportion (1:4:8) in foundation and floors using 4 cm. size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar of approved quality and from approved quarry including hoisting, lowering, laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15 cm. thick in each layer including cost, conveyance, royalties, taxes of all materials and cost of all labours, T&P etc required for the work including shoring, shuttering and dewatering if required including hire & running charges of all machineries required for the work etc complete as per the direction of the Engineer -in -charge	28.743	1 Cum.	4347.60	INR Rupees Four Thousand three hundred fourty Seven and Sixty Paise Only	124963.00	
2	Providing 16 mm thick cement plaster to the surface of brick masonry wall with cement mortar (1:6) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and levels as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge	689.348	1 Sqm	180.80	INR Rupees One hundred Eighty and Paise Eighty Only	124634.00	
3	Providing 6 mm thick cement plaster to the surface of RCC wall with cement mortar (1:4) including racking out joints, scraping and cleaning the surface and finishing the plaster surface smooth using wooden floats only to proper plumbs and levels as per drawings including cost of all materials, conveyance, loading and unloading, all taxes and royalties, all labour, scaffolding, watering and curing, sundries and T&P etc. complete as per direction of the Engineer-in-charge	313.534	1 Sqm	141.50	INR Rupees One hundred Fourty One and Paise Fifty Only	44365.00	
4	Providing laying Marble Tiles in Floors Treads of Premium quality grade in floor of Size of approved make and patterns as described with bed of 25 mm thick cement mortar 1:1(1 Cement : 1 Mortar) including grouting the joints with slurry and matching pigments ,watering curring etc comp[letely	324.964	1 Sqm	897.40	INR Rupees Eight hundred Ninety Seven and Paise Fourty Only	291623.00	

5	Providing fitting fixing up MS Grills in Windows and Framed iron plates fixed doors including transportation cost to work site ,fabrication cost ,fitting fixed as per direction of Engineer in Charge	1050.000	1 Kg	75.00	INR Rupees Seventy Five Only	78750.00
6	Providing cement washing two coats on the plaster surface of walls in all floors at all heights using required quantity of cement including watering and curring and making the surface smooth with cost, conveyance, loading, unloading, and taxes of all materials, cost of all labour, sundries, T&P, scaffolding etc. required for the work complete in all respect as directed by Engineer-in-charge	1002.882	1 Sqm	20.30	INR Rupees Twenty and Paise Thirty Only	20359.00
7	Providing and Painting 2 Coats with Acrylic wall putty (Water based) approved quality and approved shade confirming to IS on plastred surface work to give an even shade including sand preparing and making the surface smooth with cost ,conveyance ,loading and unloading and taxes of all materials ,cost of all labour, Sundries,T & P scaffolding etc required for the work complete in all respect as per directed in Engineer in Charge	1002.820	1 Sqm	67.90	INR Rupees Sixty Seven and Paise Ninety Only	68091.00
8	Providing and painting two coats with weather coat paint of approved quality and approved shade confirming to ISI on Plastered surface work to give an even shade including sand papering and making the surface smooth with cost, coveyance, loading and unloading and taxes of all materials, cost of all labour, sundries, T&P, scaffolding etc. required for the work complete in all respect as directed by Engineer-in-charge	342.500	1 Sqm	66.70	INR Rupees Sixty Six and Paise Seventy Only	22845.00
9	Providing painting 2 Coats with Plastic Emulsion Paint of approved quality and approved shade confirmming to ISI on Plastered surface work to give an even shade including sand papering and making the surface smooth with cost, coveyance, loading and unloading and taxes of all materials, cost of all labour, sundries, T&P, scaffolding etc. required for the work complete in all respect as directed by Engineer-in-charge	660.382	1 Sqm	71.40	INR Rupees Seventy One and Paise Fourty Only	47151.00

10	Enamel Painting 2 Coats over a coat of Primer of approved quality and from approved quarry including cost, conveyance, royalties, taxes of all materials and cost of all labours, T&P etc required for the work including hire & running charges of all machineries required for the work etc complete as per the direction of the Engineer -in -charge	79.988	1 Sqm	174.10	INR Rupees One Hundred Seventy Four and Paise Ten Only	13926.00
Total estimated cost in Figures :-						836707.00
	Say					836707.00
A	Add C.G.S.T. @ 6%					50202.00
B	Add S.G.S.T.@ 6%					50202.00
						937111.00
					SAY	937111.00
Amount in words(Rupees Nine Lakhs Thirty Seven Thousand One Hundred Eleven)only						

Bid of Quantities consisting of 10 (Ten) items only consisting of 3 (Three) pages.

APPROVED

**Asst Executive Engineer
Bhubaneswar Block**

**Block Development Officer
Bhubaneswar Block**

Rate quoted by Tenderers

1..... ()		Percentage Excess over the
2..... ()		Percentage less than the
3..... ()		Percentage as per the the

OFFICE USE ONLY

- 1 Total no of corrections:
- 2 Total no of overwritings:
- 3 Total no of insertions:
- 4 E.M.D. Rs..... Duly pledged/unpledged
- 5 Clearance of GST furnished / not furnished
- 6 PAN furnished/not furnished
- 7 Others.

