

# GOVERNMENT OF ODISHA

## Tender Inviting Authority: Panchayat Samiti ,Bhubaneswar

Name of Work: " Construction and Development of Road at Nandan Vihar ,Kalarahang G.P.Bhubaneswar Block "

Bid identification No: - Panchayat Samiti , Bhubaneswar /03/18-19

Bidder Name:

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate(in Rs.)		Amount	
				Figure	Words	Rs.	P
1	2	3	4	5	6	7	
<b>A- CIVIL WORK</b>							
1	Earthwork in excavation of <b>foundation &amp; plinth</b> in all kinds of soil including dressing and levelling the bed up to the required depth & removing the excavated earth & depositing the same away from the work site within initial lead of 50 mtr & initial lift of 1.5 mtr, including cost of labour T&P articles required for the work including shoring, shuttering, propping & dewatering if required, etc. complete in all respect as per the specification & direction of the Engineer-in-Charge.	341.723	1 Cum.	167.81	INR Rupees One Hundred Sixty Seven and Paise Eighty One Only	57345.00	
2	Supplying, <b>filling</b> in foundation and plinth with <b>sand</b> including watering and ramming, including cost, conveyance, royalties, taxes of the materials and labour with T&P required for the work etc. complete as directed by the Engineer-in-Charge	37.931	1 Cum.	446.80	INR Rupees Four hundred Forty Six and Paise Eighty Only	16948.00	
3	Providing and laying plain <b>cement concrete</b> of proportion <b>(1:3:6)</b> in foundation and floors using 4 cm. size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar of approved quality and from approved quarry including hoisting, lowering, laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15 cm. thick in each layer including cost, conveyance, royalties, taxes of all materials and cost of all labours, T&P etc required for the work including shoring, shuttering and dewatering if required including hire & running charges of all machineries required for the work etc complete as per the direction of the Engineer -in -charge	37.931	1 Cum.	4347.60	INR Rupees Four Thousand Fourty Seven and Paise Sixty Only	164909.00	

4	R.C.C. work of M - 20 having minimum compressive strength (in work test) 200kg./cm <sup>2</sup> in 15cm cubes at 28 days after mixing and test conducted in accordance with I.S. 456 and I.S. 516 using 12mm to 20mm size (1/2" to 3/4") crusher broken hard black granite chips of 20mm size (not to exceed 25%) of approved quality & from approved quarry including hoisting, lowering, laying and compacting concrete with vibrator, watering and curing for 28 days, cost of rigid and smooth centering & shuttering and finishing to exposed surface smooth providing, grooves or beads wherever necessary as per direction of the Engineer-in-charge including cost, conveyance, royalties & taxes of all materials and cost of all labour, T&P etc. as required for the work complete in all respects as per direction of Engineer-in-charge but excluding cost of M.S. rod/Tor steel and binding wires and labour charges for bending, binding and tying the grills etc complete as drawing design and direction of Engineer-in-charge.					
	<b>Drain</b>	122.044	1 Cum.	8653.80	INR Rupees Eight Thousand Six hundred Fifty Three and Paise Eighty Only	1056144.00
5	Providing, Cutting, straightening coiled or bent up Fe-500 grade steel (SAIL make) welding or jointing if necessary, bending, binding, tying the grills as required for RCC works, and hoisting, lowering and placing in proper position according to approved designs and drawings including cost, conveyance, loading, unloading, taxes of M.S. rods, Fe-500 or equivalent and binding wires of 18 to 20 gauge required for the work and cost of all labour, sundries, T&P and scaffolding complete in all respect as directed by the Engineer-in-Charge (payment will be made according to the actual weight of M.S. rod, Fe-500 or equivalent consumed in the work and no separate payment will be made towards weight of binding wires which is to be borne by the contractor at his own cost) as per the direction of Engineer-in-charge.	73.500	1 Ql.	6444.70	INR Rupees Six thousand Four hundred forty Four and paise Seventy only	473685.00
<b>Total estimated cost in Figures :-</b>						<b>1769031.00</b>
	<b>Say</b>					<b>1769031.00</b>
<b>A</b>	<b>Add C.G.S.T. @ 6%</b>					<b>106142.00</b>
<b>B</b>	<b>Add S.G.S.T.@ 6%</b>					<b>106142.00</b>
						<b>1981315.00</b>
					SAY	<b>1981315.00</b>
<b>Amount in words(Rupees Ninetten Lakhs Eighty One Thousand Three hundred Fifteen )only</b>						

Bid of Quantities consisting of 05 ( Five ) items only consisting of 2 (Two ) pages.

APPROVED

Asst Executive Engineer  
Bhubaneswar Block

Block Development Officer  
Bhubaneswar Block

**Rate quoted by Tenderers**

1..... ( )		<i>Percentage Excess over the</i>
2..... ( )		<i>Percentage less than the</i>
3..... ( )		<i>Percentage as per the the</i>

**OFFICE USE ONLY**

- 1 Total no of corrections:
- 2 Total no of overwrittings:
- 3 Total no of insertions:
- 4 E.M.D. Rs..... Duly pledged/unpledged
- 5 Clearance of GST furnished / not furnished
- 6 PAN furnished/not furnished
- 7 Others.

