

OFFICE OF THE MUNICIPAL COUNCIL, JATNI

QUOTATION DOCUMENT

Name of the work : Renovation of Wirings and Installation of Light Fitting and New Modular Type switch boards at Jatni Town Hall and Illumination of path light fittings various location under Jatni Municipality, Khordha.

Issued to : -----

Cost of Quotation Paper; Rs-

(Rupees.....) only

Deposited vide M.R/D.D No..... dt.....

Quotation Paper

Renovation of Wirings and Installation of Light Fitting and New Modular Type switch boards at Jatni Town Hall and Illumination of path light fittings various location under Jatni Municipality, Khordha.

Sl. No.	Description of items.	Qty	Rate	Unit	Amount in Rs
1	Recessed wiring to light point/Fan point/ Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal box having front Modular cover of suitable size, metal box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection. (Make of wire-L&T/ Anchor/ Havells/ V-Guard/ Great White/ HPL)				
a	Group-A -L.P- 11 F.P- C.B.P-	11		Point	
b	Group-B L.P- 15 F.P- 5 C.B.P-	20		Point	
c	Group-C L.P- 29 F.P- 7 C.B.P-	36		Point	
2	Recessed extra lead submain wiring alongwith earth wire with the following sizes of PVC insulated single core multistrand copper conductor ISI marked conforming to IS-694/1990 in 20mm dia non metallic heavy duty flexible conduit 1.6 mm in recessed PVC conduit as required (make of wire -Finolex/ L&T/ Anchor/Havells/V-Guard /Great White/HPL) exceeding to Group-C points in 2 X 1.5sqmm +1 x 1.5sqmm	189		Mtr.	
3	Recessed wiring to submain in the following sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked conforming to IS-694/1990 in the following mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with the following sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as required. (Make of wire-Finolex/ L&T/ Anchor/ Havells/ V-Guard/ HPL)				
a	2 X 2.5 sq.mm +1 X 1.5 sq.mm -do-	225		Mtr.	
4	Supply and fixing of 6Amp plug with 6Amp switch on existing board. (Modular type)(Make-Great white/ Legrand / Roma/ Havells/ HPL/ Cona)	31		Each	
5	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 6Amp switch and socket of Modular type including all connection. (Make-Great white/ Legrand / Roma/ Havells/ HPL/ Cona)	11		Each	
6	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 6pin 6Amp & 16Amp socket outlet and 16Amp Modular switches connection. (Make-Great	4		Each	

	white/ Legrand / Roma/ Havells/ HPL/ Cona)				
7	Supply and fixing of Electronics step type Modular fan regulator. (Make-Great white/ Legrand / Roma/ Havells/ HPL/ Cona)	6		Each	
8	Supply and fixing of Modular switch ,Socket , T.V Socket and Telephone socket etc. (Make-Great white/ Legrand / Roma/ Havells/ HPL/ Cona)				
a	10 Amp switch (Modular type)	85		Each	
b	10 Amp socket(Modular type)	12		Each	
c	20 Amp switch (Modular type)	5		Each	
d	20 Amp socket.(Modular type)	5		Each	
e	Modular blank plate	18		Each	
f	Modular Neon Indicator	3		Each	
9	Supply and fixing of Modular metal box of following size (nominal size) on surface/Recess with suitable size of Modular cover in front including cutting the wall and making good the same in cases of recessed conduit as required (Modular box + cover+ fixing + Labour cess) (Make-Great white/ Legrand / Roma/ Havells/ HPL/ Cona)				
a	2 Modulee	10		Each	
b	4 Modulee	2		Each	
c	6 Modulee	22		Each	
d	8 Modulee	1		Each	
10	Supply and fixing of changeover switch (Anchor/Havells/Apex/Benlo)				
a	32 Amp Changeover switch	2		Nos.	
11	S/F of 60Watt LED GATE light fitting (Make-Crompton/Havells/Equi)	2		Nos.	
a	S/F of Gate light jally duly fabricated at well mounted with C.C masonry work etc.	2		Nos.	
b	S/F of GI bracket	2		Nos.	
12	Supply and fixing 25 watt LED street light fitting. (Make- Havells/ Phillips/ Bajaj/ Crompton)	2		Nos.	
13	S/F of 18W LED surface fitting (Make- Havells/ Phillips/ Bajaj/ Crompton)	13		Nos.	

14	Supply and fixing 30 watt LED Flood light fitting. (Make- Havells/ Phillips/ Bajaj/ Crompton)	12		Nos.	
15	Supply and Fixing of 7 watt LED spot light fitting. (Make- Havells/ Phillips/ Bajaj/ Crompton)	7		Nos.	
16	Supply and Fixing of 9 Watt LED Bulb (Make: HPL/Havells/Crompton/Philips)	15		Nos.	
17	Supply and Fixing of 12 Watt LED Bulb (Make: HPL/Havells/Crompton/Philips)	6		Nos.	
18	Recessed wiring to submain in the following sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked conforming to IS-694/1990 in the following mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with the following sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as required. (Make of wire-Finolex/ L&T/ Anchor/ Havells/ V-Guard/ HPL)				
a	2 X 4 sq.mm +1 X 1.5 sq.mm -do-	249		Mtr.	
19	Supply and fixing of copper plate earthing (600 X 600 X 3.15mm) with running copper flat 25 X 5mm (2 run) from copper plate to funnel of 40mm dia G.I pipe including all accessories as per the direction of Engineer-in-charge.	1		Each	
a	S/F of 8 SWG Cu wire	17		Mtr.	
20	Supply and fixing of fan (make-Usha/Orient/V-Guard/Khaitan/Havells/ Crompton/ Almonard/				
a	A.C Ceiling fan 48" (Crompton Greaves High Speed Aluminium body copper winding)/Crompton(model-Jura)/polycab(model-Vital)/Polar(model-Winpro))/etc.)	6		Nos.	
b	Exhaust fan 10"/12" size	6		Nos.	
c	Wall mounted fan (24") (Make-Almonard, Havels, Crompton)	12		Nos.	
21	S/F of 32 AMP DP MCB including box (L & T, Legrand & simens)	2		Each	
22	1.5sqmm 3 core copper cable (Make-Finolex,V Guard,L & T,Havells & HPL)	120		Mtr.	
23	40 watt LED post top light(Crompton,Havells)	12		Nos.	
24	Pole 200 x 200 x 10mm with Fittings	12		Nos.	
25	S/F of No.8 G.I wire as earth continuity	12		Kg	
26	S/F of PVC pipe for wiring	65		Mtr.	
27	Supply of PVC Aluminium armored cables ISI marked (Make-Glowstar/Polycab/Nicco/KEI) 6sq.mm 2 core	254		Mtr.	
28	Cement concrete 1:1:5:3 including cost of labour T & P etc for installation of LED post in different location	12		Cum	
29	S/F of 32 AMP DP MCB including box (L & T, Legrand & simens)	2		Each	

30	1.5sqmm 3 core copper cable (Make-Finolex,V Guard,L & T,Havells & HPL)	70		Mtr.	
31	40 watt LED post top light(Crompton,Havells)	12		Nos.	
32	Pole 200 x 200 x 10mm with Fitting	12		Nos.	
33	S/F of No.8 G.I wire as earth continuity	12		Kg	
34	S/F of PVC pipe for wiring	56		Mtr.	
35	Supply of PVC Aluminium armored cables ISI marked (Make-Glowstar/Polycab/Nicco/KEI) 6sq.mm 2 core	365		Mtr.	
36	Cement concrete 1:1:5:3 including cost of labour T & P etc for installation of LED post in different location	12		Cum	
	Total				
	Add 12% GST				
	Grand total				
	Or Say				

Sold to Sri..... Who has deposited Rs.....

Rupees)only vide MR No.....date.....

towards cost of Tender paper.

Executive Officer,
Jatni Municipality

E.M.D deposited Rs.....

Vide MR No-

Date.....

Copy of ITCC-----Furnished / not

Copy of GST CC ----- Furnished / not

No of Correction -----

No of Over writing-----

No of Addition-----

Signature of Quotationer

Executive Officer,
Jatni Municipality